

MODEL:PSP-600-27

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1: 240 mVp-p (Max)	I/P: 230VAC O/P:FULL LOAD Ta:25°C	V1: 87 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 24V - 30 V	I/P: 230 VAC I/P: 115 VAC O/P:MIN LOAD Ta:25°C	21.5 V~ 32.6 V/ 230 VAC 21.5 V~ 32.6 V/ 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1: 1 %~ -1 % (Max)	I/P: 155 VAC / 264 VAC O/P:FULL/ MIN LOAD Ta:25°C	V1: 0.15 %~ -0.15 %	P
4	LINE REGULATION	V1: 0.5 %~ -0.5 % (Max)	I/P: 155VAC ~ 264 VAC O/P:FULL LOAD Ta:25°C	V1: 0.03 %~ -0.03 %	P
5	LOAD REGULATION	V1: 0.5 %~ -0.5 % (Max)	I/P: 230 VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: 0.15 %~ -0.15 %	P
6	SET UP TIME	230VAC: 1500 ms (Max) 115 VAC: 1500 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 901 ms 115VAC/ 901 ms	P
7	RISE TIME	230VAC: 50 ms (Max) 115VAC: 50 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 5 ms 115VAC/ 5 ms	P
8	HOLD UP TIME	230VAC: 16 ms (TYP) 115VAC: 16 ms(TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 23 ms 115VAC/ 23 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST: <5 %	P
10	DYNAMIC LOAD	V1: 2700 mVp-p	I/P: 230 VAC O/P:FULL /Min LOAD 90%DUTY/1KHZ Ta:25°C	687 mVp-p	P

INPUT FUNCTION TEST

N O	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	88VAC~264 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	60V~264V	P
			I/P: LOW-LINE-3V= 85 V HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST: OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P: 88 VAC ~ 264 VAC O/P:FULL-MIN LOAD Ta:25°C	TEST: OK	P
3	POWER FACTOR	0.95 / 230 VAC (TYP) 0.98 / 115 VAC (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	PF= 0.96 / 230 VAC PF= 0.99 / 115 VAC	P
4	EFFICIENCY	86% (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	88.3 %	P
5	INPUT CURRENT	230V/ 4.1 A (TYP) 115V/ 8.2 A (TYP)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 3.2 A/ 230 VAC I = 6.4 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 50 A(TYP) 115V/ 25 A(TYP) COLD START	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 34 A/ 230 VAC I = 18 A/ 115 VAC	P
7	LEAKAGE CURRENT	< 1.5 mA / 240 VAC	I/P: 254 VAC O/P:Min LOAD Ta:25°C	L-FG: 1.05 mA N-FG: 1.05 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105%~ 135 %	I/P: 230 VAC I/P: 115 VAC O/P: TESTING Ta:25°C	118 %/ 230 VAC 118 %/ 115 VAC Foldback Current Limiting	P
2	OVER VOLTAGE PROTECTION	CH1: 31 V~ 36.5 V	I/P: 230 VAC I/P: 115 VAC O/P: MIN LOAD Ta:25°C	33.7 V/ 230 VAC 33.7 V/ 115 VAC Shunt down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC: TSW1: 85± 5°C O.T.P TSW2: 80± 5°C O.T.P NO DAMAGE	I/P: 230 VAC O/P: FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down , than re-power on to recover	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264 VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Foldback Current Limiting	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	FAN SPEED CONTROL	-----	I/P: 230 VAC O/P: FULL LOAD Ta:25°C	Fan Voltage= 11.08 V	P
2	REMOTE CONTROL	Rc+ / Rc- SHORT POWER ON OPEN POWER OFF	I/P: 230 VAC O/P: FULL LOAD Ta:25°C	SHORT POWER ON OPEN POWER OFF	P
3	POWER OK	POWER ON : 3.3V~6V POWER OFF : 0V~2V	I/P: 230 VAC I/P: 115 VAC O/P: FULL LOAD Ta:25°C	POWER ON : 4.89 V POWER OFF : 0 V	P
4	CURRENT SHARING	PSU1-PSU2 < 10%	I/P: 230 VAC O/P: FULL/50% LOAD Ta:25°C	O/P: 100% PSU1: 678 W PSU2: 724 W O/P: 50% PSU1: 336 W PSU2: 368 W	P
5	REMOTE SENSE	>0.3V	I/P: 230 VAC O/P: FULL LOAD Ta:25°C	>0.3V	P

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 3 KVAC/min I/P-FG: 1.5 KVAC/min O/P-FG: 0.5 KVAC/min	I/P-O/P: 3.6 KVAC/min I/P-FG: 1.8 KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P: 7.17 mA I/P-FG: 6.36 mA O/P-FG: 4.8 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P: 11 GΩ I/P-FG: 6 GΩ O/P-FG: 5 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta:25°C	8 mΩ	P
4	APPROVAL	TUV: Certificate NO : R50051249 UL: File NO : E183223			P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 LIGHT INDUSTRY L-N :1KV L,N-PE:2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				



M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	SUPPOSE C205 IS THE MOST CRITICAL COMPONENT I/P: 230VAC O/P:FULL LOAD Ta= 25 °C LIFE TIME= 2220955 HRS I/P: 230VAC O/P:FULL LOAD Ta= 45 °C LIFE TIME= 655699 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE: 116.4K HRS			P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 52 Rated 2SK2850 : 900 V 6 A	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 748 V (2) 800 V (3) 776 V	P
2	Diode Peak Voltage	D 72 Rated D9202 : 200V 20A	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on (2) Full Load (3)Output Short Ta:25°C	(1) 126 V (2) 135 V (3) 134 V	P
3	Clamp Diode Peak Voltage	D 50 Rated UF5408 3A/1KV	I/P:High-Line +3V = 267 V O/P: (1)Full Load (2) Dynamic Load 90%Duty/1KHz Ta:25°C	(1) 768 V (2) 768 V	P
4	Input Capacitor Voltage	C5 Rated :150 u / 400V/ 85°C	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 382 V (2) 382 V (3) 382 V	P
5	Control IC Voltage Test	U50 Rated 3845 : 30V	I/P:High-Line +3V = 267 V O/P: (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta:25°C	(1) 16.8 V (2) 15.2 V (3) 16.7 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2004/8/13	RD SMAPLE	PASS	VINCENT TSENG	MAX LIN
2004/11/9	PRODUCT SAMPLE W0409A42	PASS	VINCENT TSENG	MAX LIN
2005/1/5	PRODUCT SAMPLE W0411C25	PASS	VINCENT TSENG	MAX LIN

2003/12/12 A50-F023